COMET Facility Report

Santa Monica, CA -

Facility Executive Summary

Report Date: 13 Aug 2001

Facility: Santa Monica Community College\Southwest Quadrant\Stadium/Maint, Oper, & Warehs

Facility Description:

ARCHITECTURAL/STRUCTURAL/FIRE PROTECTION/ACCESSIBILITY

The Stadium is located in the southwest quadrant of the campus adjacent to 16th street. The 5,500 +/- capacity stadium was originally constructed in 1925. In addition to the school's athletic events (football and soccer games, and track and field events), the stadium is used by the community at large for annual jazz festivals and 4th of July fireworks displays. Maintenance workshops and warehouses are located under the concrete stadium's bench seating. The shop facilities include electrical, plumbing, metal shop, and carpentry. The shipping and receiving warehouse and mezzanine was constructed in 1983.

The ceiling above the maintenance shops has sustained several leaks. The most recent epoxy re-sealing occurred in 1983 at the roof over the metal shop. Approximately 33% of the reinforced concrete beams sustained noticeable damage in the 1994 earthquake and were repaired in 1996 with epoxy injection.

The public restrooms (men and women) are located on grade level adjacent to 16th street and are both ADA accessible.

MECHANICAL

Two (2) air-handling units (AHU) supply the heating and cooling for the 3-story portion of this complex. For cooling the AHU's are served with chilled water by two (2) 226-ton chillers and four (4) circulating pumps located in the basement, and two (2) roof top cooling towers served by two (2) circulating pumps. For heating the AHU's are served with hot water by three (3) natural gas fired boilers located in a rooftop mechanical room.

Two (2) AHU's supply the heating and cooling for the 2-story portion of this complex. The AHU's are served with chilled and hot water from the same source as the 3-story complex. Part of the 2-story portion is not served with cooling. Additional heating for the 2-story portion is provided by reheat units at each zone.

There is no re-circulated air in this complex. All air is exhausted by several large central exhaust systems. There is a Carrier Energy Management System that serves the complex. All controls are pneumatic with air provided from a rooftop mechanical room compressor. All mechanical equipment is two years old and in excellent condition.

ELECTRICAL

The electrical system is fed from a 2500 KVA transformer that delivers 277/480 volt, 3-phase power via a 4000-amp panel that is located in the basement of the 3-story building. This panel provides power to numerous other panels and transformers located throughout the complex, and a 300 KVA emergency stand-by diesel generator set located at ground level adjacent to the complex. The transformers are of various sizes and provide 120/208 volt, 3-phase power to numerous panels located electrical rooms throughout the complex. The 480-volt power serves all major electrical equipment through motor control centers. The 277-volt power serves complex lighting, most of which is fluorescent with electronic ballasts and T-8 lamps. The 120-volt power serves miscellaneous small equipment and electrical outlets throughout the complex.

The stand-by generator is a self-contained unit that has a built-in 600-gallon fuel tank. This generator will provide power to all essential equipment and lighting that is wired into system in the event of a power failure. The exterior lighting is controlled by a Microlite Lighting Control system. All electrical equipment is two years old and in excellent condition.

PLUMBING

The plumbing system consists of low flush toilets and valves. Domestic hot water is provided from natural gas fired boilers and circulating pumps that are located in a rooftop mechanical room. There is a sump pump in the basement. All plumbing equipment is two years old and in excellent condition.

Photographer:

WEden

Date:

13-Jul-2001

Repair Costs:

\$1,542,981.93

Replacement Cost:

\$5,047,509.81

FCI:

30.57%



Photo Description:

Stadium, Southwest Quadrant

Santa Monica, CA

COMET Facility Report

Facility Cost Summary

st Summary


Report Date: 13 Aug 2001

Southwest Quadrant - Stadium/Maint, Oper, & Warehs

Gross Area: 23,236 SF


				Cost	Replacement	Life	%	Renewal		Next	Adjustment	Year 2001	
System Group	System Description	Priority	Discrepancy	Sq. Foot	Cost	Years	Renewed	Cost	% Used	Renewal	Amount	Estimate	FCI %
Code/Life/Saf	Fire	-		\$6.27	\$145,690	8	130.00%	\$189,397	100.00%	2001	\$0	\$189,397	
	Subtotal			\$6.27	\$145,690			\$189,397			80	\$189,397	130.00%
Flectrical	Comm/Data/Security	-		\$4.70	\$109,139	10	%00.06	\$98,226	40.00%	2007	0\$	80	
	Electrical Service	-		\$3.82	\$88,692	30	%00.06	\$79,823	10.00%	2028	\$0	0\$	
	Lighting/Circuits	-		\$18.83	\$437,580	20	%00.06	\$393,822	20.00%	2017	80	\$0	
	Subtotal			\$27.35	\$635,412			\$571,870			80	S	%00.0
Ext. Closure	Doors and Windows	•		\$12.45	\$289,335	30	110.00%	\$318,268	100.00%	2001	9	\$318,268	
	Exterior Walls	-		\$39.53	\$918,612	100	100.00%	\$918,612	%00.09	2041	20	05	
	Roofing	,		\$8.42	\$195,531	20	120.00%	\$234,637	100.00%	2001	80		
	Subtotal			\$60.40	\$1,403,478			\$1,471,517			0\$	\$552,905	39.40%
Interiors	Ceilings	-		\$7.40	\$172,016	15	110.00%	\$189,218	100.00%	2001	90	\$189,218	
	Floor	-		\$7.06	\$164,093	15	110.00%	\$180,502	100.00%		80	\$180,502	
	Wall Finish	-		\$7.92	\$184,029	10	100.00%	\$184,029	75.00%	2003	0\$	80	
	Walls/Doors	-		\$16.71	\$388,250	4	%00.06	\$349,425	100.00%	2001	0\$		
1	Subtotal			\$39.09	\$908,388			\$903,174			0\$	\$719,145	79.17%
Mech / Plumb.	Air/Ventilation	,		\$10.81	\$251,251	20	100.00%	\$251,251	10.00%	2019	0\$	80	
	Heating/Cooling			\$25.91	\$601,929	25	100.00%	\$601,929	20.00%		0\$		
	Plumbing/Fixtures	-		\$3.51	\$81,535	30	100.00%	\$81,535	100.00%	2001	\$0		200
1	Subtotal			\$40.23	\$934,715			\$934,715			\$0	\$81,535	8.72%
Specialties	Built-in Furn/Appliances	-		\$7.40	\$172,016	20	100.00%	\$172,016	80.00%	2005	0\$		
	Subtotal			\$7.40	\$172,016			\$172,016			0\$	80	0.00%
Structural,	Found./Slab/Structure	-		\$36.49	\$847,812	100	100.00%	\$847,812	43.00%	2058	0\$		
	Subtotal			\$36.49	\$847,812			\$847,812			80		
1	Grand Total			\$217.23	\$5,047,510			\$5,090,501			0\$	\$1,542,982	30.57%

Future Facility Funding vs FCI for Stadium/Maint, Oper, & Warehs



COMET - Printed on: 8/13/01 Escalation %: 3%

Estimate by Building System - Stadium/Maint, Oper, & Warehs



COMET - Printed on: 8/13/01

COMET Facility Report

Santa Monica, CA

Facility Executive Summary

Report Date: 13 Aug 2001

Facility: Santa Monica Community College\Southeast Quadrant\Student Activities

Facility Description:

ARCHITECTURAL/STRUCTURAL/FIRE PROTECTION/ACCESSIBILITY

Student Activities and Cayton Center is located in the southeast quadrant of the campus north of the clock tower quad. The 2 story, 57,041 square foot facility houses the following activities: faculty dining at the "Bread Factory", student dining commons, "Carl's Jr.", Health Center, Study Hall, Computer Lab, and KCRW public radio station. The structure was originally constructed in 1952; the 2nd floor, 12,390 square foot Cayton Center was added in 1990. The student dining area was remodelled in 1993, the scope of the remodel included new lighting, sheet vinyl flooring and repainting the walls and ceiling. The lighting in Study Hall was replaced and upgraded in 2001.

The building rests on spread footings that are showing no signs of damage or settlement. The building structural system was constructed of poured in place reinforced concrete exterior walls. The interior walls are wood studs with metal lathe and cement plaster. The exterior storefront system and doors are single pane glazing with metal frames. The original roofing system was replaced with "monoform" in 1976 and is experiencing minor leaks.

The interior building finishes are painted drywall, flooring in the high traffic area is sheet vinyl. The roof over the Student Activities Center has numerous leaks.

The building is not fire sprinklered but has a centrally monitored Simplex fire alarm system utilizing both fire annunciators and strobes.

The building complies with accessibility requirements for the ramping to the main entrance and mens' and womens' toilets, however the elevator is not ADA compliant.

MECHANICAL

The complex is a series of buildings, additions, and remodels that contain a variety of systems of different ages. The basement contains radio station KCRW and is fully air conditioned by several different systems that have been installed at various times.

The west portion of the basement system is chilled water with no heat and was installed in approximately 1990. All equipment appears to be in good condition. The air handler is located in a basement mechanical room. The chiller is mounted on the roof. The east portion of the basement system is split system heat pump and was installed in approximately 1991. All equipment appears to be in good condition. The air handler is located in a basement mechanical room. The condenser is mounted on the roof. The KCRW office area has a newly installed HVAC system with condensers mounted outside at ground level.

The health office has a self-contained roof mounted HVAC unit of approximately 5 tons and is approximately 12 years old. The bookstore, student dining room, and the second floor are supplied by hot water heat-vent systems fed by natural gas fired boilers in the basement. The hot water boilers were replaced in 1991 and are in good condition. The staff lounge is currently being renovated and contains a stand-alone roof mounted HVAC unit of approximately 7 tons and is approximately 10 years old.

There are several food vendors that have stand-alone systems that serve their individual spaces. These systems are serviced and maintained by the food vendors.

There are several roof mounted toilet exhaust fans of various ages.

ELECTRICAL

The electrical system for this complex is fed from two transformers. The original unit is 200 KVA, installed in 1952, and provides120/208 volt, 3-phase power to most of the building via an 800-amp distribution panel. The transformer, along with most of the feeder and distribution wiring for the facility, is beyond its expected life and should be replaced, A 300 KVA transformer was added to accommodate the needs of KCRW in 1993, and provides 120/208 volt, 3-phase power via a 1000-amp panel that is located in a ground mounted electrical room. This 1000-amp panel provides power to smaller panels located within the basement. This electrical room also contains a self-contained 75 KVA diesel powered generator that provides back up power to the critical loads for the radio station. This unit was installed by KCRW in 2000.

The lighting system for this complex is of various types and ages. Most of the lighting is fluorescent. The vapor lighting system on the second floor in inefficient and should be replaced with fluorescent fixtures. The student dining area was remodeled in approximately 1990, new fixtures were installed, and are in good condition. Other portions of the complex contain fluorescent fixtures that have exceeded their useful life and should be replaced. A portion of the second floor received new fluorescent lighting with T-8 lamps and electronic ballasts this year.

There is an emergency central battery backup system that is not functioning. This system was designed to provide emergency power to exit signs and some additional building lighting. This unit has exceeded its useful life and should be replaced.

PLUMBING

The plumbing system, as with the other systems, is of different ages and conditions. There is a sewer lift station that serves the basement restroom facilities. The pumps appear to have been replaced and the system is working properly. A grease interceptor system was installed in 1990 to provide for grease collection from the various food vendors.

Domestic hot water is supplied from a natural gas fired water heater located in the basement.

There is no fire sprinkler system in this building

COMET Facility Report

Santa Monica, CA

Facility Executive Summary

Report Date: 13 Aug 2001

Facility: Santa Monica Community College\Southeast Quadrant\Student Activities

Photographer: WEden

Date: 13-Jul-2001

Repair Costs: \$804,962.59

Replacement Cost: \$12,480,000.39

FCI: 6.45%



Photo Description:

Student Activities, Southeast Quadrant

Santa Monica, CA

Report Date: 13 Aug 2001

COMET Facility Report


Facility Cost Summary

Southeast Quadrant - Student Activities

Gross Area: 57,041 SF

				Cost	Replacement	Life	%	Renewal		Next	Adjustment	Year 2001	
System Group	System Description	Priority	Discrepancy	Sq. Foot	Cost	Years	Renewed	Cost	% Used	Renewal	Amount	Estimate	FCI %
Code/Life/Saf	Fire Sprinkler	-		\$3.18	\$181,390	20	120.00%	\$217,668	100.00%	2001	0\$	\$217,668	
	Subtotal			\$3.18	\$181,390			\$217,668			0\$	\$217,668	120.00%
Electrical	Comm/Data/Security	-		\$3.28	\$187,094	20	100.00%	\$187,094	10.00%	2019	05	0\$	
	Electrical Service	-		\$3.10	\$176,827	3	80.00%	\$141,462	10.00%	2028	0\$	0%	
	Lighting/Circuits	-		\$20.40	\$1,163,636	9	100.00%	\$1,163,636	10.00%	2028	80	0%	
	Subtotal			\$26.78	\$1,527,558			\$1,492,193			\$ 0	80	0.00%
Ext. Closure	Doors and Windows	-		\$11.45	\$653,119	20	100.00%	\$653,119	20.00%	2017	%	0\$	
	Exterior Walls	-		\$24.05	\$1,371,836	20	100.00%	\$1,371,836	40.00%	2031	80	80	
	Roofing	-		\$8.58	\$489,412	20	120.00%	\$587,294	100.00%	2001	80	\$587,294	
	Subtotal			\$44.08	\$2,514,367			\$2,612,250			0\$	\$587,294	23.36%
Interiors	Ceilings	-		\$5.65	\$322,282	9	100.00%	\$322,282	10.00%	2010	0\$	0\$	
	Floor	-		\$9.60	\$547,594	9	100.00%	\$547,594	10.00%	2010	80	0\$	
	Wall Finish	-		\$6.06	\$345,668	10	100.00%	\$345,668	%00.09	2005	8 0	80	
	Walls/Doors	-		\$15.31	\$873,298	20	100.00%	\$873,298	%00.09	2009	80	80	
	Subtotal			\$36.62	\$2,088,841			\$2,088,841			80	80	%00.0
Mech / Plumb.	Plumbing/Fixtures	-		\$4.46	\$254,403	8	100.00%	\$254,403	20.00%	2025	%	80	
	Subtotal			\$4.46	\$254,403			\$254,403			80	80	%00.0
Specialties	Built-in Furn/Appliances	-		\$38.41	\$2,190,945	20	100.00%	\$2,190,945	20.00%	2041	S	80	
	Subtotal			\$38.41	\$2,190,945			\$2,190,945			0\$	\$0	%00.0
Structural,	Found./Slab/Structure	-		\$28.52	\$1,626,809	100	100.00%	\$1,626,809	%00.09	2041	%	80	
	Subtotal			\$28.52	\$1,626,809			\$1,626,809			0\$	\$0	%00.0
Unknown	Cooling	-		\$31.62	\$1,803,636	30	80.00%	\$1,442,909	10.00%	2028	0\$	90	
	Site Utilities	-		\$2.77	\$158,004	20	100.00%	\$158,004	70.00%	2016	0\$	\$0	
	Special Systems	-		\$2.35	\$134,046	30	100.00%	\$134,046	80.00%	2007	80	80	
	Subtotal			\$36.74	\$2,095,686			\$1,734,959			0\$	0\$	%00.0
	Grand Total			\$218.79	\$12,480,000			\$12,218,068			o s	\$804,963	6.45%


₩ 10.0% - 8.0% Future Facility Funding vs FCI for Student Activities Current FCI = 6.45% \$1,200,000 \$1,000,000 \$800,000 Funding Amount



FCI%

COMET - Printed on: 8/13/01 Escalation %: 3%

Estimate by Building System - Student Activities



COMET - Printed on: 8/13/01

COMET Facility Report

Santa Monica, CA

Facility Executive Summary

Report Date: 13 Aug 2001

Facility: Santa Monica Community College\Southeast Quadrant\Science

Facility Description:

ARCHITECTURAL/STRUCTURAL/FIRE PROTECTION/ACCESSIBILITY

The Science Building is located in the southeast quadrant of the campus, east of the Clocktower quad. The original Science Building that occupied the current site was damaged beyond repair in the 1994 Northridge Earthquake and required complete demolition. The current 98,400 square foot facility was constructed in 1999. The three (3) story eastern wing houses labs and classrooms, and the two (2) story western wing houses faculty and administrative offices as well as classrooms and lecture halls.

The building rests on spread footings and isolated concrete column bases that are showing no signs of damage or settlement. The building's structural system was constructed of steel frames with cement plaster exterior skin. The interior walls are metal studs with drywall. The exterior storefront system is dual glazed with metal frames. The western wing roof is constructed of standing seam metal roofing and it experiences severe leaking at the outboard gutter locations.

The interior finishes include 12" x 12" ceramic tile in lobby areas, sheet vinyl in the laboratories, and carpet in the lecture halls. The ceiling treatment is primarily 24" x 24" regular lay-in ceiling tiles.

The fire alarm system consists of strobes and alarms in all corridors and other public areas. The "Simplex" system is centrally monitored, and the building is completely fire sprinklered. The building is entirely ADA accessible with exterior ramps, interior accessible elevators and men and women's toilet rooms.

MECHANICAL

Two (2) air-handling units (AHU) supply the heating and cooling for the 3-story portion of this complex. For cooling the AHU's are served with chilled water by two (2) 226-ton chillers and four (4) circulating pumps located in the basement, and two (2) roof top cooling towers served by two (2) circulating pumps. For heating the AHU's are served with hot water by three (3) natural gas fired boilers located in a rooftop mechanical room.

Two (2) AHU's supply the heating and cooling for the 2-story portion of this complex. The AHU's are served with chilled and hot water from the same source as the 3-story complex. Part of the 2-story portion is not served with cooling. Additional heating for the 2-story portion is provided by reheat units at each zone.

There is no recirculated air in this complex. All air is exhausted by several large central exhaust systems. There is a Carrier Energy Management System that serves the complex. All controls are pneumatic with air provided from a rooftop mechanical room compressor. All mechanical equipment is two years old and in excellent condition.

ELECTRICAL

The electrical system is fed from a 2500 KVA transformer that delivers 277/480 volt, 3-phase power via a 4000-amp panel that is located in the basement of the 3-story building. This panel provides power to numerous other panels and transformers located throughout the complex, and a 300 KVA emergency stand-by diesel generator set located at ground level adjacent to the complex. The transformers are of various sizes and provide 120/208 volt, 3-phase power to numerous panels located electrical rooms throughout the complex. The 480-volt power serves all major electrical equipment through motor control centers. The 277-volt power serves complex lighting, most of which is fluorescent with electronic ballasts and T-8 lamps. The 120-volt power serves miscellaneous small equipment and electrical outlets throughout the complex.

The stand-by generator is a self-contained unit that has a built-in 600-gallon fuel tank. This generator will provide power to all essential equipment and lighting that is wired into system in the event of a power failure. The exterior lighting is controlled by a Microlite Lighting Control system. All electrical equipment is two years old and in excellent condition.

PLUMBING

The plumbing system consists of low flush toilets and valves. Domestic hot water is provided from natural gas fired boilers and circulating pumps that are located in a rooftop mechanical room. There is a sump pump in the basement. All plumbing equipment is two years old and in excellent condition.

Photographer:

WEden

Date:

13-Jul-2001

Repair Costs:

\$202,130.00

Replacement Cost: \$23,064,960.00

FCI:

0.88%



Photo Description:

Science. Southeast Quadrant

COMET Facility Report

Facility Cost Summary


Report Date: 13 Aug 2001

Southeast Quadrant - Science

Santa Monica, CA

Gross Area: 98,400 SF

				Cost	Replacement	Life	%	Renewal		Next	Adjustment	Year 2001	
System Group	System Description	Priority	Discrepancy	Sq. Foot	Cost	Years	Renewed	Cost	% Used	Renewal	Amount	Estimate	FCI %
Active	Superstructure	-		\$1.09	\$107,256	100	100.00%	\$107,256	10.00%	2091	0\$	0\$	700
	Subtotal			\$1.09	\$107,256			\$107,256			0\$	80	%00.0
Code/Life/Saf	Fire Sprinkler	-		\$3.65	\$359,160	20	120.00%	\$430,992	10.00%	2019	90	\$0	
	Subtotal			\$3.65	\$359,160			\$430,992			0\$	0\$	%00.0
Electrical	Comm/Data/Security	-		\$1.56	\$153,504	20	100.00%	\$153,504	10.00%	2019	80	0\$	
	Electrical Service	-		\$3.11	\$306,024	30	80.00%	\$244,819	10.00%	2028	000	80	
	Lighting/Circuits	-		\$19.15	\$1,884,360	3	100.00%	\$1,884,360	10.00%	2028	80	0\$	
	Subtotal			\$23.82	\$2,343,888			\$2,282,683			0\$	0\$	%00.0
Ext. Closure	Doors and Windows	-		\$7.78	\$765,552	20	100.00%	\$765,552	10.00%	2019	80	0\$	
	Exterior Walls	-		\$3.90	\$383,760	9	100.00%	\$383,760	10.00%		0\$	000	
	Roofing	-	Gutters are leaking	\$10.55	\$1,038,120	20	120.00%	\$1,245,744	10.00%	2019	\$202,130	\$202,130	
	Subtotal			\$22.23	\$2,187,432			\$2,395,056			\$202,130	\$202,130	9.24%
Interiors	Ceilings	•		\$8.81	\$866,904	10	100.00%	\$866,904	10.00%	2010	80	S	
	Floor	-		\$11.83	\$1,164,072	9	100.00%	\$1,164,072	10.00%	2010	0\$	90	
	Wall Finish	-		\$10.85	\$1,067,640	10	100.00%	\$1,067,640	10.00%	2010	80	0\$	
	Walls/Doors	-		\$20.12	\$1,979,808	20	100.00%	\$1,979,808	10.00%	2019	80	80	
	Subtotal			\$51.61	\$5,078,424			\$5,078,424			80	0\$	0.00%
Mech / Plumb.	Plumbing/Fixtures			\$50.95	\$5,013,480	40	100.00%	\$5,013,480	10.00%	2037	\$0	80	
	Subtotal			\$50.95	\$5,013,480			\$5,013,480			\$0	0\$	%00.0
Specialties	Built-in Furn/Appliances	57		\$2.93	\$288,312	30	100.00%	\$288,312	10.00%	2028	80	80	
	Subtotal			\$2.93	\$288,312			\$288,312			0\$	80	0.00%
Structural,	Found /Slab/Structure	-		\$39.95	\$3,931,080	100	100.00%	\$3,931,080	10.00%	2091	80	0\$	
es.	Subtotal			\$39.95	\$3,931,080			\$3,931,080			%	0\$	0.00%
Unknown	Cooling	7		\$38.17	\$3,755,928	30	80.00%	\$3,004,742	10.00%	2028	80	80	200000000000000000000000000000000000000
	Subtotal	8		\$38.17	\$3,755,928			\$3,004,742			80	\$0	
	Grand Total			\$234.40	\$23,064,960			\$22,532,026			\$202,130	\$202,130	0.88%



COMET - Printed on: 8/7/01 Escalation %: 3%

Estimate by Building System - Science



COMET - Printed on: 8/7/01

COMET Facility Report

Santa Monica, CA

Facility Executive Summary

Report Date: 13 Aug 2001

Facility: Santa Monica Community College\Northwest Quadrant\Technology

Facility Description:

ARCHITECTURAL/STRUCTURAL/FIRE PROTECTION/ACCESSIBILITY

The Technology Building is located in the northwest quadrant of the campus. The three- story, 111,145 square foot facility was originally constructed in 1969. The first two floors contain classrooms, laboratory facilities, and lecture halls, while the third floor contains offices and the computer data rooms. The second floor was remodelled in 1989 and the third floor was added in 1992. This facility houses technology as well as vocational courses.

The building rests on spread footings and shows no signs of damage or settlement. The building's structural system was constructed of poured in place reinforced concrete walls with reinforced (board-marked) concrete infill as well as some CMU infill. The interior studs are metal with painted gyp. board. Ceiling finishes include perforated metal and painted gypsum board. The exterior storefront system and doors are single pane glazing in metal frames with some operable units.

The interior finishes include carpeting and resilient flooring in the lobby, carpet and resilient flooring in the classrooms, and ceramic tile in the restrooms. The roofing is a membrane system which was replaced in 1992 and has no leaks.

This facility has a state of the art fire sprinkler system and a centrally monitored fire alarm system, which are interconnected. Additionally, the building is handicap compliant, and has handicap accessible toilets.

MECHANICAL

This building contains several different types of HVAC equipment depending on when the addition was completed or the area was remodeled. The basement boiler room provides hot water for heating and consists of four (4) natural gas fired hot water boilers and six (6) circulating pumps. All of this equipment is five years old.

The rooftop contains two (2) 100-ton chilling units and pumps. The York unit serves the third floor and is scheduled for replacement. The Carrier unit serves a portion of the first floor and the entire second floor, is four years old.

A rooftop mounted multi-zone air-handling unit (AHU) serves the third floor heating and cooling. This AHU is provided chilled water from the above-mentioned York unit. Individual zone reheat units that are supplied with hot water from the basement boiler room provide heat. The third floor system design was never adequate and is inefficient because of the high ceilings and extensive use of glass. The HVAC system for this floor should be redesigned and replaced.

A third floor mechanical room contains the AHU that serves the second floor. This AHU has a new cooling coil served with chilled water from the roof mounted Carrier chiller. The heat coil within the AHU has been disconnected. Individual zone reheat units that are supplied with hot water from the basement boiler room provide heat.

The first floor shop areas contain AHU's that are ceiling hung and serve each individual space. The heat coils within the AHU's are supplied with hot water from the basement boiler and provide heat. Outside air is ducted through the AHU to provide ventilation. Most of this equipment is 32 years old, obsolete and outdated, beyond its useful life, and should be replaced. Room T-100 has a new roof mounted natural gas fired heat/vent unit. Rooms T-101 A&B each have a new 3-ton package unit.

A roof mounted exhaust fan serving auto and photo shops on the first floor has just been replaced. Additional roof mounted exhaust fans of various ages and serving toilets and special classroom needs appear to be functioning properly and are within normal life expectancy.

MCC's are located in the boiler room, second floor mechanical room, and on the rooftop, are providing power to the localized equipment. Most of the building HVAC controls are pneumatic. Some of the building is DDC.

ELECTRICAL

The electrical system is fed from an SCE transformer that delivers 277/480 volt, 3-phase power via a 3000-amp distribution panel located on the ground floor within the shop area. This panel provides power to numerous other panels and transformers located throughout the complex, and a new, small, emergency stand-by, self contained, diesel generator set, located at ground level adjacent to the building, that provides power to the third floor computer area. The transformers are of various sizes and provide 120/208 volt, 3-phase power to numerous panels located electrical rooms throughout the building. The 480-volt power serves all major electrical equipment through motor control centers. The 277-volt power serves building lighting. Fluorescent with electronic ballasts and T-8 lamps serves most of the second floor. T-12 fluorescent lights serve most of the third floor. The first floor has a mixture of T-8 and T-12 consisting of different ages and serving various areas. The 120-volt power serves miscellaneous small equipment and electrical outlets throughout the complex. There are also some transformers providing 120/240 volt, 1-phase power to older parts of the building.

Most of the distribution equipment has served its useful life, is obsolete, and should be replaced. The fluorescent fixtures on the first floor with T-12 lamps have served their useful life, are obsolete, and should be replaced.

PLUMBING

The plumbing system - piping and fixtures - for this building is of different ages and conditions. The building has low flush toilets. The majority of faucets are seven years old. There is a sump pump in the basement and a clarifier serves the auto shop area.

Two 75-gallon natural gas fired water heaters and a circulating pump provide domestic hot water. This system is seven years old.

COMET Facility Report

Santa Monica, CA

Facility Executive Summary

Facility: Santa Monica Community College\Northwest Quadrant\Technology

Photographer: WEden

Date:

13-Jul-2001

Repair Costs: \$2,520,768.60

Replacement Cost: \$26,052,388.00

FCI: 9.68%



Report Date: 13 Aug 2001

Photo Description:

Technology, Northwest Quadrant

Santa Monica, CA

COMET Facility Report Facility Cost Summary

Report Date: 13 Aug 2001

Northwest Quadrant - Technology


Gross Area: 111,145 SF

		-		Cost	Replacement	Life	%	Renewal		Next	Adjustment	Year 2001	
System Group	System Description	Priority	Discrepancy	Sq. Foot	Cost	Years	Renewed	Cost	% Used	Renewal	Amount	Estimate	FCI %
Active	Sup	-		\$1.09	\$121,148	100	100.00%	\$121,148	20.00%	2051	\$0	\$0	
	Subtotal			\$1.09	\$121,148			\$121,148			80	80	%00.0
Code/I ife/Saf	Fire Sprinkler	*		\$3.65	\$405,679	20	120.00%	\$486,815	80.00%	2005	80	0\$	
	Subtotal			\$3.65	\$405,679			\$486,815			o s	80	%00.0
Flectrical	Comm/Data/Security	-		\$1.56	\$173,386	20	100.00%	\$173,386	80.00%	2005	80	80	
	Flectrical Service			\$3.11	\$345,661	38	80.00%	\$276,529	80.00%	2007	\$0	80	
	Liahting/Circuits	+		\$19.15	\$2,128,427	3	100.00%	\$2,128,427	%00.09	2016	80	80	
	Subtotal			\$23.82	\$2,647,474			\$2,578,342			0\$	0\$	%00.0
Ext Closure	Doors and Windows	-		\$7.78	\$864,708	20	100.00%	\$864,708	80.00%	2005	90	80	
	Exterior Walls	·+		\$3.90	\$433,466	9	100.00%	\$433,466	80.00%	2013	80	90	
	Roofing	-		\$10.55	\$1,172,580	20	120.00%	\$1,407,096	80.00%	2005	80	\$0	
1	Subtotal			\$22.23	\$2,470,753			\$2,705,269			0\$	\$0	%00.0
Interiors	Cellinas	-		\$8.81	\$979,187	1	100.00%	\$979,187	80.00%	2003	0\$	80	
	Floor	-		\$11.83	\$1,314,845	9	100.00%	\$1,314,845	100.00%	2001	0\$	\$1,314,845	
	Wall Finish	-		\$10.85	\$1,205,923	9	100.00%	\$1,205,923	100.00%	2001	80	\$1,205,923	
	Walls/Doors	-		\$20.12	\$2,236,237	20	100.00%	\$2,236,237	80.00%	2005	80	80	
	Subtotal			\$51.61	\$5,736,193			\$5,736,193			80	\$2,520,769	43.94%
Mech / Plumb.	Plumbing/Fixtures	-		\$50.95	\$5,662,838	40	100.00%	\$5,662,838	80.00%	5003	0\$	80	
	Subtotal			\$50.95	\$5,662,838			\$5,662,838			0\$	0\$	%00.0
Specialties	Built-in Furn/Appliances	-		\$2.93	\$325,655	30	100.00%	\$325,655	80.00%	2007	80	80	
	Subtotal			\$2.93	\$325,655			\$325,655			0\$	0\$	%00.0
Structural,	Found./Slab/Structure	-		\$39.95	\$4,440,243	100	100.00%	\$4,440,243	80.00%	2021	80	80	
	Subtotal			\$39.95	\$4,440,243			\$4,440,243			0\$	0\$	%00.0
Unknown	Cooling	-		\$38.17	\$4,242,405	30	80.00%	\$3,393,924	80.00%	2007	80	80	2000
	Subtotal			\$38.17	\$4,242,405			\$3,393,924	1		\$0	80	%00.0
1	Grand Total			\$234.40	\$26,052,388			\$25,450,427			0\$	\$2,520,769	%89'6

FCI% - 10.0% - 8.0% %0.9 -4.0% - 2.0% **~**0.0 -2001/2002/2003/2004/2005/2006/2007/2008/2009/2010/2011/ Future Facility Funding vs FCI for Technology — FCI% Progress 3 Funding Plan 3 Current FCI = 9.68% — FCI% Progress 2 Funding Plan 2 Year - FCI% Progress 1 Funding Plan 1 \$8,000,000 -\$2,000,000 -\$1,000,000 (\$1,000,000) \$4,000,000 -\$5,000,000 \$6,000,000 \$3,000,000 -\$0 \$7,000,000 Funding Amount

COMET - Printed on: 8/7/01 Escalation %: 3%

Estimate by Building System - Technology



COMET Facility Report

Santa Monica, CA

Facility Executive Summary

Report Date: 13 Aug 2001

Facility: Santa Monica Community College\Southeast Quadrant\Admissions

Facility Description:

ARCHITECTURAL/STRUCTURAL/FIRE PROTECTION/ACCESSIBILITY

The Admissions building is located in the southeast quadrant of the campus, adjacent to Pearl Street and is a one-story, 18,014 square foot facility that houses Admissions, Records and Counseling. Additionally, Admissions employs an open office design utilizing desk clusters; Records and Counseling use individual offices.

The building rests on spread footings that are showing no signs of damage or settlement. The building structural system was constructed of reinforced concrete exterior walls. The interior walls are wood studs with metal lathe and cement plaster. The exterior strorefront system and doors are single pane glazing with metal frames. The original roofing system was replaced with "monoform" in 1976 and is experiencing minor leaks.

The interior building finishes contain asbestos in the ceiling tile mastic and floor tile mastic that cover approximately 50% of the building. The balance of the building floor area is covered with substandard carpeting in the offices.

The building doesn't have: fire sprinklers, strobes, annunciators, nor a functioning fire alarm system. Additionally, 50% of the exterior single pane windows contain asbestos, and the building is not handicap compliant.

MECHANICAL

The heating system consists of baseboard style radiators that are served with hot water from three (3) natural gas fired boilers in the basement. Some of the baseboard radiators are not functioning due to malfunctioning valves. The radiators, boilers, and piping are obsolete and beyond their expected useful life, and should be replaced and upgraded.

There are two (2) split system cooling units rated at 3 tons each. The condensing units are roof mounted and serve the air-handlers below. These systems are inadequately sized, beyond their useful life, and do not provide sufficient cooling for the building. Open windows and portable electric fans provide fresh air ventilation. The toilet exhaust fan is roof mounted, functioning but beyond its useful life, and should be replaced.

ELECTRICAL

The electrical system is fed from a 300KVA transformer that delivers 120/208 volt, 3-phase power via an 800-amp panel, all located in the basement. This 800-amp panel provides power to smaller panels located within the building. Most of the feeder and distribution wiring for the facility is beyond its expected life and should be replaced.

The building lighting system has not been upgraded. The fluorescent lighting with T-12 lamps is beyond its useful life and should be replaced. Emergency exit signs contain individual battery backup power and appear to have served their useful life.

PLUMBING

The plumbing system - piping and fixtures - is original and though functioning adequately is beyond its expected useful life. Domestic hot water is supplied from a natural gas fired water heater located in the basement. The sewer main line serving this building is subject to frequent blockages that require roto-rootor service several times each year and should be replaced.

Photographer: WEden

Date:

13-Jul-2001

Repair Costs: \$1,518,552.18

Replacement Cost: \$2,305,875.22

FCI: 65.86%



Photo Description:

Admissions, Southeast Quadrant

Report Date: 13 Aug 2001

COMET Facility Report Facility Cost Summary

Southeast Quadrant - Admissions

Santa Monica, CA

Gross Area: 10,615 SF

0.00				Cost	Replacement	Life	%	Renewal		Next	Adjustment	rear 2001	100000000000000000000000000000000000000
System Group	System Description	Priority	Discrepancy	Sq. Foot	Cost	Years	Renewed	Cost	% Used	Renewal	Amount	Estimate	FCI %
Code/Life/Saf	Fire Sprinkler	5	Non existant, retrofit program currentl	\$6.27	\$66,556	30	130.00%	\$86,523	100.00%	2001	0\$	\$86,523	
	Subtotal			\$6.27	\$66,556			\$86,523			80	\$86,523	130.00%
Flectrical	Comm/Data/Security	4		\$4.70	\$49,859	10	%00.06	\$44,873	100.00%	2001	80	\$44,873	
	Electrical Service	8	Exceed 150% of est. life	\$3.82	\$40,517	30	%00.06	\$36,466	100.00%	2001	90	\$36,466	
	Lighting/Circuits	8	150% of est. life cycle	\$18.83	\$199,902	20	%00.06	\$179,912	100.00%	2001	0\$	\$179,912	
	Subtotal			\$27.35	\$290,278			\$261,250			0\$	\$261,250	%00.06
Ext Closure	Doors and Windows	4		\$12.45	\$132,178	8	110.00%	\$145,396	100.00%	2001	80	\$145,396	
	Exterior Walls	9		\$39.53	\$419,653	100	100.00%	\$419,653	49.00%	2052	0\$	\$0	
	Roofina	e	Minor leaks are occuring	\$8.42	\$89,325	20	120.00%	\$107,190	100.00%	2001	0\$	\$107,190	
	Subtotal			\$60.40	\$641,157			\$672,239			0\$	\$252,586	39.40%
Interiors	Ceilings	4	Mastic contains asbestos	\$7.40	\$78,583	15	110.00%	\$86,441	100.00%	2001	8	\$86,441	
	Floor	4	Mastic contains asbestos	\$7.06	\$74,963	15	110.00%	\$82,459	100.00%	2001	0\$	\$82,459	
	Wall Finish	4		\$7.92	\$84,071	9	100.00%	\$84,071	100.00%	2001	0\$	\$84,071	
	Walls/Doors	4		\$16.71	\$177,366	40	%00.06	\$159,629	100.00%	2001	80	\$159,629	
	Subtotal			\$39.09	\$414,983			\$412,601			\$0	\$412,601	99.43%
Mech / Plumb.	Air/Ventilation	8	150% of est. life cycle	\$10.81	\$114,780	20	100.00%	\$114,780	100.00%	2001	0\$	\$114,780	
	Heating/Cooling	4		\$25.91	\$274,982	25	100.00%	\$274,982	100.00%	2001	0\$	\$274,982	
	Plumbing/Fixtures	2	150% of est. life cycle	\$3.51	\$37,248	8	100.00%	\$37,248	100.00%	2001	\$0	\$37,248	
	Subtotal			\$40.23	\$427,010			\$427,010			80	\$427,010	100.00%
Specialties	Built-in Furn/Appliances	4		\$7.40	\$78,583	20	100.00%	\$78,583	100.00%	2001	80	\$78,583	
	Subtotal			\$7.40	\$78,583			\$78,583			0\$	\$78,583	100.00%
Structural,	Found./Slab/Structure	9		\$36.49	\$387,310	100	100.00%	\$387,310	49.00%	2052	80	\$0	
	Subtotal			\$36.49	\$387,310			\$387,310			80	\$0	%00.0
	Grand Total			\$217.23	\$2,305,875			\$2,325,515			0\$	\$1,518,552	65.86%


FCI% %0.08 → -20.0% - 10.0% %0.07 **□ ~0.09 –** - 50.0% **~**0.0 **–** 12001120021200312004120051200612007120081200912010120111 Future Facility Funding vs FCI for Admissions — FCI% Progress 3 Funding Plan 3 Current FCI = 65.86% Funding Plan 2

— FCI% Progress 2 Year Funding Plan 1

FCI% Progress 1 \$400,000 \$50,000 -20 Funding Amount \$250,000 -\$300,000 \$350,000 \$100,000

COMET - Printed on: 8/7/01 Escalation %: 3%

Estimate by Building System - Admissions



COMET - Printed on: 8/13/01